QUOTE

 # QT-000139

Jerry Reed Excavating
15401 New Rd
Mishawaka Indiana 46544
U.S.A
5742981361
jreed15401@gmail.com

Bill To
CENTRE TWP TRUSTEE

: Jul 07, 2026

Subject :

RETENTION POND 19971 KERN RD

#	Item & Description	Qty	Rate	Amount
1	DIG RETENTION POND 10' WIDER AND 10' LONGER HAUL EXTRA DIRT OFF SITE DIG 4' DEEPER IN CENTER BOTTOM INSTALL 2' OF 5C STONE IN BOTTOM OF DUG AREA RELINE DISTURBED BANKS WITH STRAW BLANKETS/RE-SEED FOR EROSION.	1.00	10,600.00	10,600.00
2	SAWCUT DRIVEWAY CONCRETE REMOVE/HAUL OFF SITE. PRICE INCLUDES LANE CLOSURE INSTALL 53 MATERIALS FOR NEW CONCRETE BASE 6" NEEDED INSTALL NEW CONCRETE WHERE NEEDED AROUND NEW DRAINS INSTALL NEW CONCRETE SLOPE TOWARDS KERN RD TO KEEP RAIN WATER OUT OF PARKING LOT. 6" INCH THICK CONCRETE INSTALL 40 FT NEENAH FRENCH DRAIN INSTALL ACO DRAIN SYSTEM TO CATCH RAIN WATER SO IT DRAINS TO KERN RD NEW FRENCH DRAIN LINE	1.00	23,768.20	23,768.20

Sub Total	34,368.20
Total	**$34,368.20**

Crafted with ease using Zoho Invoice
Visit zoho.com/invoice to create truly professional invoices

Notes

Looking forward for your business.

Terms & Conditions

Half balance is due when starting job.
Remaining balance due at completion.